

PROJECT WASTE MANAGEMENT

MASTER SPECIFICATION

APRIL 7, 1998
REVISED APRIL, 2001

Prepared by Susan Morris Specifications Limited
under Contract to Greater Vancouver Regional District

DISCLAIMER: THE HEALTH AND SAFETY OF WORKERS AND THE PUBLIC ARE THE FIRST PRIORITY IN ANY CONSTRUCTION OR DEMOLITION PROJECT. PROJECT OWNERS ARE RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE CODES AND STATUTORY OR REGULATORY REQUIREMENTS. THIS SPECIFICATION IS NOT INTENDED TO CONSTITUTE OR RENDER ENGINEERING, ARCHITECTURAL, LEGAL OR OTHER PROFESSIONAL SERVICES OR ADVICE OR SHOULD IT BE A SUBSTITUTE FOR SUCH SERVICES OR ADVICE FROM AN EXPERIENCE PROFESSIONAL DIRECTED TO THE SPECIFIC DESIGN SITUATION. WHILE THE INFORMATION IN THE SPECIFICATION IS BELIEVED TO BE ACCURATE, THE GVRD AND SUSAN MORRIS SPECIFICATIONS LIMITED SHALL NOT BE LIABLE FOR DAMAGES ARISING FROM ERRORS OR OMISSIONS IN THIS SPECIFICATION.

SECTION 01505 - PROJECT WASTE MANAGEMENT

PART 1 - GENERAL

1.1 WASTE MANAGEMENT GOALS FOR THE PROJECT

- .1 The Owner has established that this Project shall generate the least amount of waste possible and that processes shall be employed that ensure the generation of as little waste as possible including prevention of damage due to mishandling, improper storage, contamination, inadequate protection or other factors as well as minimizing over packaging and poor quantity estimating,
- .2 Of the inevitable waste that is generated, the waste materials designated in this specification shall be salvaged for reuse and or recycling. Waste disposal in landfills or incinerators shall be minimized. On new construction projects this means careful recycling of job site waste, on demolition projects this also means careful removal for salvage.

1.2 SECTION INCLUDES

- .1 Submission and implementation of a Project Waste Management Plan.

1.3 RELATED SECTIONS

- .1 Section 02050 - Deconstruction
- .2 Section 02200 - Earthwork
- .3 Section 02870 - Site Furnishings
- .4 Section 02900 - Landscaping
- .5 Section 03100 - Concrete Formwork
- .6 Section 03300 - Cast-In-Place Concrete
- .7 Section 05100 - Structural Metal Framing
- .8 Section 05400 - Light Gauge Metal Framing
- .9 Section 06100 - Rough Carpentry
- .10 Section 06200 - Finish Carpentry Cabinets, Countertops
- .11 Section 06300 - Wood Treatment
- .12 Section 07200 - Building Insulation
- .13 Section 08800 - Glazing / Windows
- .14 Section 09250 - Gypsum Board
- .15 Section 09300 - Tile Work

- .16 Section 09550 - Wood Flooring
- .17 Section 09650 - Resilient Flooring
- .18 Section 09680 - Carpet
- .19 Section 09900 - Painting

1.4 CODE OF PRACTICE

- .1 In addition to other requirements specified herein it is a requirement for the Work of this project that the Contractor comply with the GVRD's "3Rs Code of Practice for the Building Industry". Refer also to "Job Site Recycling: A Guide for Builders and Developers" and "Demolition & Salvage: A Guide for Developers and Renovators." All documents are available from the GVRD, Policy and Planning Department, Telephone: 604-437-GVRD(4873). Website address: www.gvrd.bc.ca/services/garbage/index.html.

1.5 REGULATORY REQUIREMENTS

- .1 Conform to applicable codes and regulations for disposal and removal of common and hazardous waste. Handle and dispose of all hazardous and banned materials in accordance with the BC Waste Management Act and Special Waste Regulation, and regional and municipal regulations. These hazardous and banned materials include but are not limited to asbestos, drywall (banned from disposal), underground storage tanks, Polychlorinated Biphenyls (PCBs), abandoned chemicals (gasoline, pesticides, herbicides, flammable and combustible substances), freon from cooling equipment, lead-based paints, smoke detectors, and mercury containing switches.
- .2 Licensed facilities: Only those brokerage, storage, transfer and disposal facilities which comply with the requirements of the "Greater Vancouver Sewerage and Drainage District Municipal Solid Waste and Recyclable Material Regulatory Bylaw No. 181, 1996 as amended by Bylaw 183, 1996" and those licensed by other jurisdictions shall be used by the Contractor for the recycling and disposal of waste materials generated at deconstruction and renovation projects.

1.6 WASTE MANAGEMENT PLAN

- .1 Waste Management Plan: Within 10 calendar days after receipt of Notice of Award of Contract, or prior to any waste removal, whichever occurs sooner, the Contractor shall submit to the Owner and Consultant a Waste Management Plan. Attached is a sample format together with sample waste generation rates to aid the Contractor in formulating the Plan. The Contractor may use this form or provide a custom form containing the same information. The Plan shall contain the following:
 - .1 Analysis of the proposed job site waste to be generated, including the types of recyclable and waste materials generated (by volume or weight). In the case of demolition, a list of each item proposed to be salvaged during the course of the project should also be prepared (Refer to the Job Site Recycling Guide for a directory of service providers. This list is not necessarily complete. The Contractor may use any of these or other service providers).
 - .2 Alternatives to Landfilling: Contractor shall designate responsibility for preparing a list of each material proposed to be salvaged, reused, or recycled during the course of the Project (Refer to the Job Site Recycling Guide, Directory section).

- .3 List of compulsory materials to be recycled, shall include, at minimum, the following materials:
 - .1 Old corrugated cardboard.
 - .2 Clean dimensional wood, palette wood.
 - .3 Concrete/Brick/Concrete Block/Asphalt.
 - .4 Scrap Metal.
 - .5 Drywall.
 - .6 Paint (return to Paint Depot).
- .4 List of additional optional materials to be recycled.
 - .1 Fluorescent tubes.
 - .2 Landclearing debris.
- .5 List of Materials to be Salvaged (Demolition Projects only)
 - .1 Dimensioned Lumber and Heavy Timbers.
 - .2 Wood siding.
 - .3 Structural Steel.
 - .4 Wood Paneling, molding, trim and Wainscoting.
 - .5 Heritage architectural elements such as mantle pieces, columns, etc.
 - .6 Cabinets and casework.
 - .7 Insulation.
 - .8 Brick and block.
 - .9 Electric Equipment and Light Fixtures.
 - .10 Plumbing fixtures and brass.
 - .11 Windows, doors and frames.
 - .12 Hardwood flooring.
- .2 Meetings: Contractor shall conduct Project Waste Management meetings. Meetings shall include subcontractors affected by the Waste Management Plan. At a minimum, waste management goals and issues shall be discussed at the following meetings:
 - .1 Pre-bid meeting.

- .2 Pre-construction meeting.
- .3 Regular job-site meetings.
- .3 Materials Handling Procedures: prevent contamination of materials to be recycled and salvaged and handle materials consistent with requirements for acceptance by designated facilities. Where space permits, source separation is recommended. Where materials must be co-mingled they must be taken to a processing facility for separation off site.
- .4 Transportation: The Contractor may engage a hauling subcontractor or self haul or make each subcontractor responsible for their own waste. In any case compliance with these requirements is mandatory.
- .5 If requested submit, to the Consultant and/or Owner way-bills, invoices and other documentation confirming that all materials have been hauled to the required locations.
- .6 Waste Management Plan Implementation:
 - .1 Manager: The Contractor shall designate an on-site party (or parties) responsible for instructing workers and overseeing and documenting results of the Waste Management Plan for the project.
 - .2 Distribution: The Contractor shall distribute copies of the Waste Management Plan to the Job Site Foreman, each Subcontractor, the Owner, and the Consultant.
 - .3 Instruction: The Contractor shall provide on-site instruction of appropriate separation, handling, and recycling to be used by all parties at the appropriate stages of the Project. On demolition projects the Contractor shall provide on-site instructions for salvage and requirements for reusing salvaged materials within the project, either in new construction or in a renovation.
 - .4 Separation facilities: The Contractor shall lay out and label a specific area to facilitate separation of materials for recycling and salvage. Recycling and waste bin areas are to be kept neat and clean and clearly marked in order to avoid contamination of materials. The requirement for separation will only be waived if the Contractor can demonstrate to the Owner/Consultant that there is insufficient room to accommodate it. If this is the case the materials must be sent to a processing facility for separation off site.
 - .5 Application for Progress Payments: The Contractor shall submit with each Application for Progress Payment a summary of waste materials, recycled, salvaged and disposed of by the Project using the form appended to this specification or a form generated by the Contractor containing the same information. Failure to submit this information shall render the Application for Payment incomplete and shall delay Progress Payment. The Summary shall contain the following information:

For each material salvaged and recycled from the Project, include the amount (in cubic yards or tonnes or in the case of salvaged items state quantities by number, type and size of items) and the destination (i.e. recycling facility, used building materials yard). For each material land filled or incinerated from the Project, include the amount (in cubic yards or tonnes) of material and the identity of the landfill, incinerator and/or transfer station.

PART 2 - PRODUCTS

- not applicable

PART 3 - EXECUTION

- not applicable

END OF SECTION 01505

Construction Projects Waste Generation Rates

Material	Residential/Commercial High-rise Construction		Institutional Low-rise Construction		Commercial Low-rise Construction		Residential Low-rise Construction	
	cu.yd./ 1,000 sq.ft.	tonnes/ 1,000 sq.ft.	cu.yd./ 1,000 sq.ft.	tonnes/ 1,000 sq.ft.	cu.yd./ 1,000 sq.ft.	tonnes/ 1,000 sq.ft.	cu.yd./ 1,000 sq.ft.	tonnes/ 1,000 sq.ft.
wood	3.3	0.40	7.0	0.86	5.6	0.68	6.0	0.73
drywall	3.6	0.92	0.9	0.22	0.2	0.05	1.1	0.27
metal	0.2	0.09	0.4	0.21	--	--	--	--
concrete/ asphalt	1.7	1.79	0.7	0.99	--	--	0.04	0.05
corrugated cardboard	--	--	--	--	7.1	0.14	2.4	0.05
other	5.6	1.54	0.2	0.54	1.0	0.27	0.5	0.14
Total	14.4	4.74	9.2	2.82	13.9	1.14	10.04	1.24

Explanatory note:

Waste generation rates vary depending on project type and size, subtrade efficiency, accurate material estimation, on-site materials storage procedures and product packaging.

Estimate the volumes or quantities of materials generated on the site by multiplying the floor area of your project with the generation rates listed for the different materials.

Waste Management Plan Construction & Demolition Projects

Name of Company	Contact Person	Telephone No.
Project Site/Location	Project Type <input type="checkbox"/> Construction <input type="checkbox"/> Demolition	Project Size (in square feet)

	Pre-Project	Project Updates	
		For Period:	to
Material	Estimated Generation	Recycled/Salvaged/Disposed	Facility
Total			

Signature	Title	Date
-----------	-------	------

Explanatory note:

Column 1 - "Material" -- enter materials targeted for recycling and/or salvage and include a category for waste materials requiring disposal

Column 2 - "Estimated Generation" -- enter estimated volumes (cu.yd.) or quantities (metric tonnes) of recyclable and waste materials generated and state number of salvageable items

Column 3 - "Recycled/Salvaged/Disposed" -- enter volumes (cu.yd.) or quantities (metric tonnes) of materials recycled and disposed and state number of items salvaged

Column 4 - "Facility" -- enter end-destination of recycled, salvaged and disposed materials.